

Research Progress of Intelligent Computing Networks in China

guoliang1@caict.ac.cn

ODCC Introduction



Open Data Center Committee (ODCC) was founded by Alibaba, Baidu, Tencent, China Telecom, China Mobile, CAICT. It now has over 100 members.



Working Groups in ODCC



There are 6 WGs and several ad-hoc task groups.













Server WG

Infrastructure WG

Network WG Edge Computing WG

Test WG

O&M WG

Wangfeng China Telecom Li Daicheng Baidu

He Zekun Tecent

Chen Wei Tecent

Guo Liang CAICT

Chao Huaipo Alibaba


Achievements in network related work





Region Scale AI Project








Region Scale AI: Challenges & Requirements



Challenge 1:


Bandwidth oversubscription in Al training network



Requirement:

Minimize traffic amount and communication times on oversubscription networks by optimizing collective communication


Challenge 2: Asymmetric transmission in collective communication



Requirement:

Model partitioning and collective communication operations are resource-aware(bandwidth, computing power, memory)

Challenge 3: Long distance transmission across DCI links




Requirement:

- Load balancing for DCI links
- DCN and DCI traffic classification
- Fast feedback and accurate congestion control mechanisms


Region Scale AI: Future Technologies




To meet the requirements of Region Scale AI, systematic innovations are needed in computing resource scheduling, collective communication, and transmission protocols.




- Resource aware model partitioning and scheduling
- Cross-AZ/cross-DC collective communication operations for DP processing
- Long-distance transmission with high-throughput and determinism
 - Lossless vs. lossy -> Control Plane lossless and Data Plane lossy




ETH-X Super POD




并行策略	数据量(一次iteration)	计算与通信是否可隐藏
DP	GB	大部分可隐藏
PP	GB	大部分可隐藏
TP	ТВ	大部分不可隐藏
SP	ТВ	大部分不可隐藏
EP	ТВ	大部分不可隐藏









ETH-X技术规范名称	进展
rack design specification	Finished
computing node design specification	Finished
switching node design specification	Finished
interconnection design specification	Finished
integration testing specification	Designing
operation and maintenance fault technical specification	Designing
business testing specification	Designing
Scale Up interconnection protocol specification	Designing
Scale Up on network computing specification	Designing


ALS (Alink System)

ALS-D: Data Plane

- · UALink (Ultra Accelerator Link) as Link protocol
- 100+TB/s interconnect bandwidth
- · 10+TB level memory fabric
- Single/multiple layer switch topology

ALS-M: Control Plane

- Standard APIs for Cloud
- Manage different vendor's fabric device
- · High flexibility



Al infra 2.0 for Alibaba Cloud







Power Supply Units

Al Compute Nodes


Fabric Nodes for ALink Scale Up Domain

Al Compute Nodes

Power Supply Units

Coolant Distribution Unit





1

High Performance

Up to 80 Al Accelerators per Rack 200kW per Rack, 2kW per Al Chip 800Gbps Scale Out BW per CIPU

2

High Energy Efficiency

Liquid Cooling Dynamic CDU, 30% energy saving HVDC, 98% power efficiency

3

ALink System (Scale-Up Domain)

64/80 accelerators via L1 Fabric 3K+ accelerators via L2 Fabric PB level memory sharing

Invitation





ISCT' 24 in Shanghai, China



THANKS